

# vit

Typst slides with View Transitions

a tutorial • press 

# A deck in ten lines

deck is the document, `slide` is a page, `mark` names what should travel. Everything else is ordinary Typst.

```
#import "@preview/vit:0.1.0": *

#deck(title: "My talk") [
  #slide [
    #set align(center + horizon)
    #mark("hi") [#text(size: 52pt)[Hello]]
  ]
  #slide [
    #mark("hi") [#text(size: 24pt)[Hello]]
    The rest of the page arrives around it.
  ]
]
```

```
typst compile --root . talk.typ talk.pdf
typst compile --root . --features html talk.typ talk.html
```



Hello

One source, two compiles: the PDF is the handout, the HTML is the deck, pixel for pixel.

# A deck in ten lines

deck is the document, `slide` is a page, `mark` names what should travel. Everything else is ordinary Typst.

```
#import "@preview/vit:0.1.0": *

#deck(title: "My talk") [
  #slide [
    #set align(center + horizon)
    #mark("hi") [#text(size: 52pt)[Hello]]
  ]
  #slide [
    #mark("hi") [#text(size: 24pt)[Hello]]
    The rest of the page arrives around it.
  ]
]
```

```
typst compile --root . talk.typ talk.pdf
typst compile --root . --features html talk.typ talk.html
```

## Hello

The rest of the page arrives around it. Two ordinary Typst pages; the only addition is the name on the word that should travel.

One source, two compiles: the PDF is the handout, the HTML is the deck, pixel for pixel.

# One question, three answers

**Did the layout change, or is one object moving?** The answer picks the API.

## Transition

The layout changed: another page, or the next frame of this one.

```
slide(..frames)
mark("key")[...]
deck/slide/mark(transition:)
```

View Transitions: the browser pairs marks by key.

# One question, three answers

Did the layout change, or is one object moving? The answer picks the API.

## Transition

The layout changed: another page, or the next frame of this one.

```
slide(..frames)
mark("key")[...]
deck/slide/mark(transition:)
```

View Transitions: the browser pairs marks by key.

## Element animation

One object varies with a parameter: the wave at its next phase.

```
mark("key", s0, s1, ...)
```

Web Animations, on the SVG nodes; stepped with → and ←.

# One question, three answers

Did the layout change, or is one object moving? The answer picks the API.

## Transition

The layout changed: another page, or the next frame of this one.

```
slide(..frames)
mark("key")[...]
deck/slide/mark(transition:)
```

View Transitions: the browser pairs marks by key.

## Element animation

One object varies with a parameter: the wave at its next phase.

```
mark("key", s0, s1, ...)
```

Web Animations, on the SVG nodes; stepped with → and ←.

## Continuous animation

Something moving on its own, with nobody pressing anything.

```
tween(play: ...) · waapi.animate
```

Web Animations, running while the page rests here.

# mark: one name, one object

The same key on two adjacent frames or pages is **one object**. The browser pairs the boxes by name and interpolates position, size and colour.

```
#slide(  
  title: "Chips",  
  [#place(dx: 20pt, dy: 20pt,  
    mark("chip")[#chip(amber, 22pt)])],  
  [#place(dx: 170pt, dy: 130pt,  
    mark("chip")[#chip(gold, 34pt)])],  
  [#place(dx: 330pt, dy: 250pt,  
    mark("chip")[#chip(cyan, 26pt)])],  
)
```



Identity is the key and only the key. Nothing is inferred from the content.

# mark: one name, one object

The same key on two adjacent frames or pages is **one object**. The browser pairs the boxes by name and interpolates position, size and colour.

```
#slide(  
  title: "Chips",  
  [#place(dx: 20pt, dy: 20pt,  
    mark("chip")[#chip(amber, 22pt)])],  
  [#place(dx: 170pt, dy: 130pt,  
    mark("chip")[#chip(gold, 34pt)])],  
  [#place(dx: 330pt, dy: 250pt,  
    mark("chip")[#chip(cyan, 26pt)])],  
)
```


A yellow rounded rectangle with a thin black border. Inside the rectangle, the word "chip" is written in a bold, black, sans-serif font.

Identity is the key and only the key. Nothing is inferred from the content.

# mark: one name, one object

The same key on two adjacent frames or pages is **one object**. The browser pairs the boxes by name and interpolates position, size and colour.

```
#slide(  
  title: "Chips",  
  [#place(dx: 20pt, dy: 20pt,  
    mark("chip")[#chip(amber, 22pt)])],  
  [#place(dx: 170pt, dy: 130pt,  
    mark("chip")[#chip(gold, 34pt)])],  
  [#place(dx: 330pt, dy: 250pt,  
    mark("chip")[#chip(cyan, 26pt)])],  
)
```



chip

Identity is the key and only the key. Nothing is inferred from the content.

# Frames and positions

Several bodies in one `slide` are **frames of one page**: one thumbnail, one dot each, `#5.1` in the address bar, and one PDF page each.

```
#let a = [ ... ]
#slide(
  title: "Frames",      // the thumbnail's caption
  note: [what to say], // the desk and the speaker view
  a,
  a + b,
  a + b + c,
)
```

5.1

5.2

5.3


A frame and an animation step are the same press, so a page' s **positions** are its frames and steps in one sequence.

Frames are for “one more line” . The page cross-fades and the marks morph: never a page jump.

# Frames and positions

Several bodies in one `slide` are **frames of one page**: one thumbnail, one dot each, `#5.2` in the address bar, and one PDF page each.

```
#let a = [ ... ]
#slide(
  title: "Frames",      // the thumbnail's caption
  note: [what to say], // the desk and the speaker view
  a,
  a + b,
  a + b + c,
)
```



A frame and an animation step are the same press, so a page' s **positions** are its frames and steps in one sequence.

Frames are for “one more line” . The page cross-fades and the marks morph: never a page jump.

# Frames and positions

Several bodies in one `slide` are **frames of one page**: one thumbnail, one dot each, `#5.3` in the address bar, and one PDF page each.

```
#let a = [ ... ]
#slide(
  title: "Frames",      // the thumbnail's caption
  note: [what to say], // the desk and the speaker view
  a,
  a + b,
  a + b + c,
)
```

5.1

5.2

5.3

A frame and an animation step are the same press, so a page' s **positions** are its frames and steps in one sequence.

Frames are for “one more line” . The page cross-fades and the marks morph: never a page jump.

# build: frames that accumulate

`build(a, b, c)` is the three frames `a`, `a + b`, `a + b + c`. Content in, content out, so it builds the body of a drawing just as well.

```
#slide(title: "How it works", ..build(  
  item("record", blue, "every marked box, where the layout..."),  
  item("draw", amber, "each one again, in a frame placed..."),  
  item("pair", green, "old against new, by name..."),  
))
```

**record** every marked box, where the layout put it

`build` when the later parts are **meant** to push the layout. When they must not, the next page.

# build: frames that accumulate

`build(a, b, c)` is the three frames `a`, `a + b`, `a + b + c`. Content in, content out, so it builds the body of a drawing just as well.

```
#slide(title: "How it works", ..build(  
  item("record", blue, "every marked box, where the layout..."),  
  item("draw", amber, "each one again, in a frame placed..."),  
  item("pair", green, "old against new, by name..."),  
))
```

**record** every marked box, where the layout put it

**draw** each one again, in a frame placed by percentage

`build` when the later parts are **meant** to push the layout. When they must not, the next page.

# build: frames that accumulate

`build(a, b, c)` is the three frames `a`, `a + b`, `a + b + c`. Content in, content out, so it builds the body of a drawing just as well.

```
#slide(title: "How it works", ..build(  
  item("record", blue, "every marked box, where the layout..."),  
  item("draw", amber, "each one again, in a frame placed..."),  
  item("pair", green, "old against new, by name..."),  
))
```

**record** every marked box, where the layout put it

**draw** each one again, in a frame placed by percentage


**pair** old against new, by name; the browser does this itself

`build` when the later parts are **meant** to push the layout. When they must not, the next page.

## reveal: frames that stay put

`reveal(n, (step, at) => ...)` writes the frames once. `at(k, x)` is `x` from frame `k` on; before that it **keeps `x`'s space**, so the layout never moves.

```
#slide(..reveal(3, (step, at) => box({
  place(dx: 0pt, dy: 0pt, cell[A])
  place(dx: 260pt, dy: 0pt, cell[B])
  place(dx: 0pt, dy: 160pt, cell[C])
  place(dx: 260pt, dy: 160pt,
    at(2, mark("d", transition: "zoom", cell[D])))
  place(dx: 138pt, dy: 44pt, // holds its box
    at(2, line(length: 114pt)))
  rect(.., stroke: at(3, 1pt)) // else none
})))
```




What has not arrived is `hidden` and holds its box; anything else is `none`, which switches a stroke off.

## reveal: frames that stay put

`reveal(n, (step, at) => ...)` writes the frames once. `at(k, x)` is `x` from frame `k` on; before that it **keeps `x`'s space**, so the layout never moves.

```
#slide(..reveal(3, (step, at) => box({
  place(dx: 0pt, dy: 0pt, cell[A])
  place(dx: 260pt, dy: 0pt, cell[B])
  place(dx: 0pt, dy: 160pt, cell[C])
  place(dx: 260pt, dy: 160pt,
    at(2, mark("d", transition: "zoom", cell[D])))
  place(dx: 138pt, dy: 44pt, // holds its box
    at(2, line(length: 114pt)))
  rect(.., stroke: at(3, 1pt)) // else none
})))
```




What has not arrived is `hidden` and holds its box; anything else is `none`, which switches a stroke off.

## reveal: frames that stay put

`reveal(n, (step, at) => ...)` writes the frames once. `at(k, x)` is `x` from frame `k` on; before that it **keeps `x`'s space**, so the layout never moves.

```
#slide(..reveal(3, (step, at) => box({
  place(dx: 0pt, dy: 0pt, cell[A])
  place(dx: 260pt, dy: 0pt, cell[B])
  place(dx: 0pt, dy: 160pt, cell[C])
  place(dx: 260pt, dy: 160pt,
    at(2, mark("d", transition: "zoom", cell[D])))
  place(dx: 138pt, dy: 44pt, // holds its box
    at(2, line(length: 114pt)))
  rect(.., stroke: at(3, 1pt)) // else none
})))
```



What has not arrived is `hidden` and holds its box; anything else is `none`, which switches a stroke off.

# Split and merge

A key that stands once on this frame and three times on the next **splits** into three; three to one **merges**. The counts need not divide.

```
#let at(x, y) = place(dx: x, dy: y, mark("cell")[#cell])

#slide(
  at(210pt, 140pt),           // one
  at(10pt, 20pt) + at(390pt, 250pt) + at(200pt, 130pt),
  at(60pt, 250pt) + at(350pt, 30pt), // three to two
  at(210pt, 140pt),           // back to one
)
```



cell

Names carry an occurrence index ( $m\text{-cell-1}$ ,  $m\text{-cell-2}$ ), so one key may stand several times.

# Split and merge

A key that stands once on this frame and three times on the next **splits** into three; three to one **merges**. The counts need not divide.

```
#let at(x, y) = place(dx: x, dy: y, mark("cell")[#cell])

#slide(
  at(210pt, 140pt),           // one
  at(10pt, 20pt) + at(390pt, 250pt) + at(200pt, 130pt),
  at(60pt, 250pt) + at(350pt, 30pt), // three to two
  at(210pt, 140pt),           // back to one
)
```

cell

cell

cell

Names carry an occurrence index ( $m\text{-cell-1}$ ,  $m\text{-cell-2}$ ), so one key may stand several times.

# Split and merge

A key that stands once on this frame and three times on the next **splits** into three; three to one **merges**. The counts need not divide.

```
#let at(x, y) = place(dx: x, dy: y, mark("cell")[#cell])

#slide(
  at(210pt, 140pt),           // one
  at(10pt, 20pt) + at(390pt, 250pt) + at(200pt, 130pt),
  at(60pt, 250pt) + at(350pt, 30pt), // three to two
  at(210pt, 140pt),           // back to one
)
```

cell

cell

Names carry an occurrence index ( $m\text{-cell-1}$ ,  $m\text{-cell-2}$ ), so one key may stand several times.

# Split and merge

A key that stands once on this frame and three times on the next **splits** into three; three to one **merges**. The counts need not divide.

```
#let at(x, y) = place(dx: x, dy: y, mark("cell")[#cell])

#slide(
  at(210pt, 140pt),           // one
  at(10pt, 20pt) + at(390pt, 250pt) + at(200pt, 130pt),
  at(60pt, 250pt) + at(350pt, 30pt), // three to two
  at(210pt, 140pt),           // back to one
)
```



cell

Names carry an occurrence index ( $m\text{-cell-1}$ ,  $m\text{-cell-2}$ ), so one key may stand several times.

# Marks nest

A mark inside a mark is a group of its own. The outer one carries what is left once the inner ones are lifted out.

```
#let nest(sz, al) = [  
  #set align(al)  
  #mark("outer")[#text(size: sz)[  
    The quick #mark("inner")[#text(fill: amber)[brown]] fox  
  ]  
]  
#slide(title: "Nested marks",  
  nest(44pt, center + horizon),  
  nest(24pt, left + top),  
)
```

The quick brown fox

Nesting is how one change's result takes part in the next **as a whole** (see layers).

# Marks nest

A mark inside a mark is a group of its own. The outer one carries what is left once the inner ones are lifted out.

```
#let nest(sz, al) = [  
  #set align(al)  
  #mark("outer")[#text(size: sz)[  
    The quick #mark("inner")[#text(fill: amber)[brown]] fox  
  ]  
]  
#slide(title: "Nested marks",  
  nest(44pt, center + horizon),  
  nest(24pt, left + top),  
)
```

The quick **brown** fox

Nesting is how one change's result takes part in the next **as a whole** (see layers).

# How a thing enters

`mark(transition:)` is **this object's own** entrance and exit. It is used only where the mark is one-sided; a mark that is on both sides morphs regardless.

```
#let definition = mark("def", transition: "wipe-down",
  env(blue)[#definition(number: "1") [...]])
#let cauchy = mark("thm", transition: "wipe-up",
  env(amber)[#theorem(number: "2") [...]])
#let cauchy-proof = mark("proof",
  transition: (enter: "wipe-left", leave: "zoom"),
  env(green)[#proof [...]])

#slide(..build(definition, cauchy, cauchy-proof))
```

**Definition 1 (Cauchy sequence).** A sequence  $(a_n)$  is **Cauchy** if for every  $\varepsilon > 0$  there is an  $N$  with  $|a_m - a_n| < \varepsilon$  whenever  $m, n > N$ .

One object, one effect: any occurrence may give it, and two may not disagree.

# How a thing enters

`mark(transition:)` is **this object's own** entrance and exit. It is used only where the mark is one-sided; a mark that is on both sides morphs regardless.

```
#let definition = mark("def", transition: "wipe-down",
  env(blue)[#definition(number: "1")[...]])
#let cauchy = mark("thm", transition: "wipe-up",
  env(amber)[#theorem(number: "2")[...]])
#let cauchy-proof = mark("proof",
  transition: (enter: "wipe-left", leave: "zoom"),
  env(green)[#proof[...]])

#slide(..build(definition, cauchy, cauchy-proof))
```

**Definition 1 (Cauchy sequence).** A sequence  $(a_n)$  is **Cauchy** if for every  $\varepsilon > 0$  there is an  $N$  with  $|a_m - a_n| < \varepsilon$  whenever  $m, n > N$ .

**Theorem 2.** A real sequence converges if and only if it is Cauchy.

One object, one effect: any occurrence may give it, and two may not disagree.

# How a thing enters

`mark(transition:)` is **this object's own** entrance and exit. It is used only where the mark is one-sided; a mark that is on both sides morphs regardless.

```
#let definition = mark("def", transition: "wipe-down",
  env(blue)[#definition(number: "1") [...]])
#let cauchy = mark("thm", transition: "wipe-up",
  env(amber)[#theorem(number: "2") [...]])
#let cauchy-proof = mark("proof",
  transition: (enter: "wipe-left", leave: "zoom"),
  env(green)[#proof [...]])

#slide(..build(definition, cauchy, cauchy-proof))
```

**Definition 1 (Cauchy sequence).** A sequence  $(a_n)$  is **Cauchy** if for every  $\varepsilon > 0$  there is an  $N$  with  $|a_m - a_n| < \varepsilon$  whenever  $m, n > N$ .

**Theorem 2.** A real sequence converges if and only if it is Cauchy.

Proof. A Cauchy sequence is bounded, so it has a convergent subsequence, and the Cauchy condition pulls the whole sequence to that limit. □

One object, one effect: any occurrence may give it, and two may not disagree.

# Page transitions

`deck(transition:)` is the default for turning to another page; `slide(transition:)` overrides it for one page. A string is the same effect both ways, `(enter:, leave:)` names the sides.

```
#deck(transition: "fade")[...]    // the default
#slide(transition: "slide")[...]  // this page only
#slide(transition: (enter: "wipe-up", leave: "fade"))[...]
#deck(transition: none)[...]      // no page transitions
```

|                                                                                               |                                                                                          |
|-----------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|
| <code>fade</code>                                                                             | cross-fade (the default)                                                                 |
| <code>slide</code>                                                                            | horizontal push; forward, the new page comes from the right                              |
| <code>rise</code>                                                                             | vertical push, in from the bottom                                                        |
| <code>zoom</code>                                                                             | the new one shrinks into place from three times life size, out of focus, and lands sharp |
| <code>wipe-left</code> <code>wipe-right</code><br><code>wipe-up</code> <code>wipe-down</code> | reveal, named by the direction the front travels                                         |
| <code>none</code>                                                                             | that side switches at once, while the transition still runs                              |

Page effects govern **unmarked** content, and only between pages. `transition: none` turns them off.

# Settings ride along

The same dictionary that names the effects carries the settings for **this** transition. Settings beside the effects belong to both sides; settings inside a side belong to that side and beat them.

```
#slide(transition: (effect: "zoom", duration: 900, zoom: 4))[...]  
  
#slide(transition: (  
  enter: (effect: "slide", duration: 200, push: -100%),  
  leave: (effect: "fade", duration: 900),  
  easing: (0.4, 0, 0.2, 1),  
))[...]  
  
#mark("word", transition: (effect: "rise", duration: 400))[...]
```


|          |                                                                                    |
|----------|------------------------------------------------------------------------------------|
| duration | milliseconds, as in deck(duration:)                                                |
| easing   | the four numbers of a cubic Bézier                                                 |
| zoom     | how many times life size the zoom starts at                                        |
| push     | how far slide and rise travel; negative goes the other way                         |
| fit      | "none" draws both images at their own size instead of stretching them into the box |
| anchor   | the corner they are pinned to when fit is none                                     |

A setting is a variable `deck.css` reads, so a typo is a compile error. Deck, slide and mark all take the same dictionary.

# Assemblies: layers

A group interpolates its **box** and cross-fades its two **pictures**. What is inside them is never moved. So what moves has to be one picture.

```
#layers("pb",
  cd({
    // the square, written once
    node((1, 0), $B$); node((1, 1), $D$)
    node((0, 0), at(2, mark("pbA", transition: "zoom")[$A$]))
    edge((0, 0), (1, 0), at(2, $p$), "->",
      stroke: at(2, 1pt + grey))
  }),
  if step >= 3 { cd({
    // X, a layer of its own,
    node((0, 0), anchor("pbA", $A$)) // the point they share
    node((-1, -1), mark("pbX", transition: "rise")[$X$])
  }) },
)
```




`reveal` keeps a picture from being re-laid-out; `layers` is for what arrives **outside** it. Name one point that is in both layers and the rest follows from the layout.

# Assemblies: layers

A group interpolates its **box** and cross-fades its two **pictures**. What is inside them is never moved. So what moves has to be one picture.

```
#layers("pb",
  cd({
    // the square, written once
    node((1, 0), $B$); node((1, 1), $D$)
    node((0, 0), at(2, mark("pbA", transition: "zoom")[$A$]))
    edge((0, 0), (1, 0), at(2, $p$), "->",
      stroke: at(2, 1pt + grey))
  }),
  if step >= 3 { cd({
    // X, a layer of its own,
    node((0, 0), anchor("pbA", $A$)) // the point they share
    node((-1, -1), mark("pbX", transition: "rise")[$X$])
  }) },
)
```




reveal keeps a picture from being re-laid-out; layers is for what arrives **outside** it. Name one point that is in both layers and the rest follows from the layout.

# Assemblies: layers

A group interpolates its **box** and cross-fades its two **pictures**. What is inside them is never moved. So what moves has to be one picture.

```
#layers("pb",
  cd({
    // the square, written once
    node((1, 0), $B$); node((1, 1), $D$)
    node((0, 0), at(2, mark("pbA", transition: "zoom")[$A$]))
    edge((0, 0), (1, 0), at(2, $p$), "->",
      stroke: at(2, 1pt + grey))
  }),
  if step >= 3 { cd({
    // X, a layer of its own,
    node((0, 0), anchor("pbA", $A$)) // the point they share
    node((-1, -1), mark("pbX", transition: "rise")[$X$])
  }) },
)
```



reveal keeps a picture from being re-laid-out; layers is for what arrives **outside** it. Name one point that is in both layers and the rest follows from the layout.


# Element animation

Several bodies are the states of one drawing: `tween(s0, s1, ...)`, or `states(...)` inside a canvas, where only what moves is a state. A drawing needs no mark: a mark is identity between pages, and this is motion inside one. → moves to the next, ← back along the same path, and the browser interpolates the SVG nodes.

```
#import "@preview/tween:0.1.0": compat
#let cz = compat.cetz.tweened(cetz) // once, per file

#let wave = cetz.canvas({
  import cetz.draw: circle, line, rect, content
  let (states,) = cz
  rect((-0.5, -2.1), (8.5, 2.1), stroke: none) // pin the box
  line((0, 0), (8, 0)) // the axis never moves
  states(..range(0, 6).map(t => { // ...these do
    let amp = 0.3 + 0.18 * t
    let f(x) = amp * calc.sin(1.2 * x - 0.5 * t)
    line(..range(0, 41).map(i => (i * .2, f(i * .2))))
    circle((1.4 * t, f(1.4 * t)), radius: .25, fill: ...)
    content((4, -1.7), [t = #t])
  })))
})

#slide[#wave]
```




The states are **one drawing under different parameters**: write  $f(t)$ , feed it a few values.

# What interpolates

The states' SVG nodes are compared one by one, and every property that differs is handed to `el.animate()`. Paths that are not the same list of commands are reconciled first.

```
// each is one canvas, and inside it one states(...)
states(..range(3, 9).map(k => polygon((0, 0), k))) // a side more
states(..range(0, 6).map(k => line(..walk.slice(0, k + 2))))
states(..range(0, 3).map(k => // a line
  if k == 0 { line((0, 0), (4, 0)) } // becomes
  else { bezier((0, 0), (4, 0), c1(k), c2(k)) })) // a curve
```



none against a colour becomes transparent. What has no in-between (text, an arc) cross-fades.

# Designing the states

Two paths interpolate point for point, so **you** choose where the new vertices come from: draw every state with the same points and stack the spare ones where they should start.

```
#let counts = (6, 12, 24, 48, 96)
#let N = counts.last() // one budget for all states
#let corners(k, r) = range(N).map(j => {
  let n = counts.at(k) // j-th point of the n-gon,
  let a = 2 * calc.pi * calc.quo(j * n, N) / n
  (r * calc.cos(a), r * calc.sin(a)) // spares stacked
})
// edges drawn as cubics: a zero-length *line* is dropped
#states(..range(0, 5).map(exhaust)) // inside the canvas
```

6 · 12 · 24 · 48 · 96



$\pi \approx 3.1410$

Same for the labels: all five counts are drawn in every state,  $\pi$  keeps four decimals.

# Dashes

`stroke-dasharray` interpolates like any other property. It is worth reaching for when what you want is **not** expressible as points: a pattern, or ink that moves along a path that stays still.

```
// gaps close: the period stays 12pt, so the dashes grow
// forward into their own gaps instead of sliding along
#let frame(f) = rect(..., stroke: (dash: (
  array: (6pt + 6pt * f, 6pt - 6pt * f), phase: 0pt)))

// ink placed anywhere on the path: an empty dash, a gap
// up to where it starts, the ink, a gap longer than the
// path. Never `phase:`: Typst writes it to
// stroke-dashoffset without flipping the sign, and the
// PDF and the browser then disagree.
#let ring = cetz.canvas(length: 1cm, {
  let (circle, over) = cz
  circle((0, 0), radius: R, stroke: (dash: (
    array: over(..range(5).map(j => (0pt,
      j / 4 * (CIRC - LEN) * 1cm, LEN * 1cm,
      2 * CIRC * 1cm))), phase: 0pt)))
}))

#tween(..range(5).map(j => frame(j / 4)))
#ring
```



the gaps close



the ink travels

Not for a line that simply grows from its end: give the states their points and let `paths.js` pad the shorter one. Reach for a dash when points cannot say it. Every state must carry the attribute (write the solid box as a zero gap, not as no dash), or the states differ in their attributes and the whole node cross-fades instead.

# Continuous animation

`waapi.animate` is Web Animations from Typst: keyframes and options as the API takes them, handed to `el.animate()` as they are. There is no DSL of our own and no deck required, so it moves the same figure in a blog post.

```
#let ball(i) = (  
  keyframes: (  
    (transform: "translateY(0)",  
      easing: "cubic-bezier(.45, 0, 1, .55)"),  
    (transform: "translateY(420%) scale(1.3, .7)",  
      offset: .5, easing: "linear"),  
    (transform: "translateY(0)"),  
  ),  
  duration: 1500, delay: i * 140,  
)  
#import "@preview/tween:0.1.0": waapi  
#for i in range(5) {  
  place(..., waapi.animate(..ball(i))[...])  
}
```



duration, delay, easing, direction, iterations; nothing plays under prefers-reduced-motion.

# follow: an element along a path

`waapi.track` names a path and `follow`: runs an element's centre along it, on the compositor. It is the one convenience in the binding.

```
#place(dx: 20pt, dy: 30pt, waapi.track("orbit", cetz.canvas({
  import cetz.draw: line
  line(..lissajous, close: true)
})))
#place(dx: 20pt, dy: 30pt, waapi.animate(
  follow: "orbit", duration: 4000,
)[#std.circle(radius: .3cm)])
#place(dx: 430pt, dy: 120pt, waapi.animate(
  keyframes: ((transform: "rotate(0)"),
              (transform: "rotate(1turn)")),
  duration: 6000,
)[#std.rect(...)])
```




Three sources of keyframes: keyframes for the mark itself, `follow` for a path, and (next page) the mark's own states.

# States played over time

Give an object an `anim`: with neither `keyframes` nor `follow`, and the **states of the drawings inside it become the keyframes**: stepping turns into playing.

```
#import "@preview/komet:0.2.0" as komet

#let coef = {                // the M largest terms of the DFT
  let n = clef.len()
  let out = ()
  for (k, z) in komet.fft(clef).enumerate() {
    let (re, im) = (z.at(0) / n, z.at(1) / n)
    out.push((n: if k * 2 <= n { k } else { k - n },
              re: re, im: im, r: calc.sqrt(re * re + im * im)))
  }
  out.sorted(key: e => -e.r).slice(0, M)
}
// epicycles(j) draws the chain at t = 2πj/S over the outline,
// whose pieces are lit by how far behind the pen they lie
// and inked by how much of them the pen has crossed
#let clef = cetz.canvas({
  let (states,) = cz
  rect((-0.83, -1.43), (0.83, 1.34)) // pin the box
  states(play: (duration: 6000), ..range(S + 1).map(epicycles))
})
#clef
```




An object animated this way counts no steps. The states are a sampling rate, and between two of them every number moves at a constant rate: anything turning faster than  $S/2$  is aliased, and geometry re-listed per state changes velocity at every keyframe. Hence 45 vectors, and a trail that is fixed pieces with moving light and moving ink.

# A seamless loop

The same mechanism, twenty-five states, and one rule of composition: make the first state and the last state equal and the loop has nowhere to jump.

```
#let sea = cetz.canvas({
  let (states,) = cz
  rect(...) // box and sun stay put
  circle((11.8, 2.2), radius: .5, fill: gold)
  states(play: (duration: 4000), ..range(0, 25).map(k => {
    let phi = k / 24 * 2 * calc.pi // 0 ... 2π over 25 states
    let surf(a, w, v, y0) = x => y0
      + a * calc.sin(w * x + v * phi)
      + a * .35 * calc.sin(2.3 * w * x - 2 * v * phi)
    ...three layers, then the boat on the front one...
  }))
})
```

#sea




iterations is infinite by default; animations pause when the frame is left.

# CeTZ

`cetz.canvas` exports native SVG paths, so a canvas in a mark pairs by key exactly as text does, and its nodes are what an element animation interpolates.

```
// CeTZ has a `mark` of its own (arrow heads), so
// `import cetz.draw: *` shadows this one by name.
#import "@preview/cetz:0.5.2"

#let fig(r) = cetz.canvas({
  import cetz.draw: circle, rect, content
  circle((0, 0), radius: r) // cetz's circle here;
  rect((-1, -1), (1, 1))    // std.circle for Typst's
  content((0, -1.7), [cetz])
})
#slide(title: "CeTZ", [#mark("fig")[#fig(0.6)]],
        [#mark("fig")[#fig(1.2)]])
```




The bounding box follows what is drawn: pin it with an invisible `rect(..., stroke: none)`.

# CeTZ

`cetz.canvas` exports native SVG paths, so a canvas in a mark pairs by key exactly as text does, and its nodes are what an element animation interpolates.

```
// CeTZ has a `mark` of its own (arrow heads), so
// `import cetz.draw: *` shadows this one by name.
#import "@preview/cetz:0.5.2"

#let fig(r) = cetz.canvas({
  import cetz.draw: circle, rect, content
  circle((0, 0), radius: r) // cetz's circle here;
  rect((-1, -1), (1, 1))    // std.circle for Typst's
  content((0, -1.7), [cetz])
})
#slide(title: "CeTZ", [#mark("fig")[#fig(0.6)]],
        [#mark("fig")[#fig(1.2)]])
```



The bounding box follows what is drawn: pin it with an invisible `rect(..., stroke: none)`.


# Third party packages

A slide is an `html.frame`, and inside a frame Typst's target is the **paged** one, so theorion and fletcher take their PDF branch and hand us a picture, which is what a mark can move.

```
#import "@preview/theorion:0.6.0": *
#import cosmos.simple: *
#import "@preview/fletcher:0.5.8" as fletcher: diagram, node, edge

#let duo(rev) = diagram({
  let arrow(a, b, l) = if rev { edge(b, a, l, "->") }
                        else   { edge(a, b, l, "->") }

  node((0, 0), $P$); node((1, 0), $B$)
  node((0, 1), $C$); node((1, 1), $D$)
  arrow((0, 0), (1, 0), $p$); ...
})
#slide[#tween(duo(false), duo(true))]
```



Mark what the package takes as **content**; its arrows are drawn, so keep the geometry still.

# Inside a formula

A mark is content and a formula is made of content, so a term is marked where it stands, passed **as an equation**, not as bare math.

```
#let sq = mark.with("sq")
#let rhs = mark.with("rhs")
#let half = mark.with("half", transition: "rise")
#let add = mark.with("add", transition: "rise")

#slide(title: "Completing the square",
  $ #sq($x^2$) + #sq($b x$) = #rhs($c$) $,
  $ #sq($x^2$) + #sq($b x$) + #half($(b/2)^2$)
    = #rhs($c$) + #add($(b/2)^2$) $,
  $ #sq($(x + b/2)^2$) = #rhs($c$) + #add($(b/2)^2$) $,
)
```

$$x^2 + bx = c$$

A box lays content out as markup, which would set  $b x$  upright; as an equation it is untouched.

# Inside a formula

A mark is content and a formula is made of content, so a term is marked where it stands, passed **as an equation**, not as bare math.

```
#let sq = mark.with("sq")
#let rhs = mark.with("rhs")
#let half = mark.with("half", transition: "rise")
#let add = mark.with("add", transition: "rise")

#slide(title: "Completing the square",
  $ #sq($x^2$) + #sq($b x$) = #rhs($c$) $,
  $ #sq($x^2$) + #sq($b x$) + #half($(b/2)^2$)
    = #rhs($c$) + #add($(b/2)^2$) $,
  $ #sq($(x + b/2)^2$) = #rhs($c$) + #add($(b/2)^2$) $,
)
```

$$x^2 + bx + \left(\frac{b}{2}\right)^2 = c + \left(\frac{b}{2}\right)^2$$

A box lays content out as markup, which would set  $b x$  upright; as an equation it is untouched.

# Inside a formula

A mark is content and a formula is made of content, so a term is marked where it stands, passed **as an equation**, not as bare math.

```
#let sq = mark.with("sq")
#let rhs = mark.with("rhs")
#let half = mark.with("half", transition: "rise")
#let add = mark.with("add", transition: "rise")

#slide(title: "Completing the square",
  $ #sq($x^2$) + #sq($b x$) = #rhs($c$) $,
  $ #sq($x^2$) + #sq($b x$) + #half($(b/2)^2$)
    = #rhs($c$) + #add($(b/2)^2$) $,
  $ #sq($(x + b/2)^2$) = #rhs($c$) + #add($(b/2)^2$) $,
)
```

$$\left(x + \frac{b}{2}\right)^2 = c + \left(\frac{b}{2}\right)^2$$

A box lays content out as markup, which would set  $b x$  upright; as an equation it is untouched.

# The deck

deck is the document. Its arguments are the only global settings there are, and the PDF and the HTML both read them.

```
#deck(  
  title: "My talk",  
  width: 1280pt, height: 720pt,  
  pdf: auto,                // the .pdf beside the .html  
  duration: 700,            // milliseconds  
  easing: (0.32, 0.72, 0, 1),  
  transition: "fade",  
  theme: auto,              // player chrome only  
  fill: rgb("#111318"),  
  font: ("DejaVu Sans", "Noto Sans CJK SC"),  
  body,  
)  
  
#slide(title: "...", note: [speaker notes], ...frames)
```

|                |                                                         |
|----------------|---------------------------------------------------------|
| title          | document title                                          |
| width / height | layout size; the PDF page and the player's aspect ratio |
| pdf            | the toolbar's download link; none removes the button    |
| duration       | default transition duration, in milliseconds            |
| easing         | the four numbers of a cubic Bézier                      |
| transition     | default page-to-page effect                             |
| theme          | light or dark player chrome                             |
| fill           | layout background, painted the same in both formats     |
| font           | font stack, glyph-by-glyph fallback                     |
| slide(title:)  | thumbnail caption; never in the layout                  |
| slide(note:)   | speaker notes; HTML only                                |

title and note are content, not just strings: paragraphs, lists and emphasis all render in the notes.

# Presenting

The player is part of the deck: no server, no build step. Open the HTML file and it is a presentation.

```
window.vit
// { go, next, prev, index, total,
//   step, steps, speed, mode, deck }
// step, speed and mode are writable;
// mode is "desk" | "present" | "overview"

const deck = document.querySelector('.vit-deck')
// the deck is at the new position, and then
// it has finished moving, one for one;
// e.detail is { index, step } for both
deck.addEventListener('vit:move-here', on)
deck.addEventListener('vit:move-done', on)
```

|             |                                                 |
|-------------|-------------------------------------------------|
| → ↓ Space   | next position: next step, next frame, next page |
| ← ↑ ⌫       | previous position                               |
| Home End    | first / last page                               |
| 1-9         | jump to a page                                  |
| Esc / Enter | desk ⇌ presenting                               |
| o / a       | overview; a dot per position, hover to peek     |
| l           | laser pointer                                   |
| b / .       | black screen                                    |
| - = 0       | slower / faster / reset, kept in localStorage   |
| s           | speaker view: next page, notes, timer           |
| f           | full screen                                     |
| ?           | this table                                      |

The desk is what opens; its preview is a copy of this HTML at a hash, so it plays the real thing.

# Choosing

Nine calls, and the question each of them answers. When two would do, the one that keeps the layout still is the one that morphs.

```
mark("key")[...]           // this thing is that thing
tween(s0, s1, ...)         // one drawing, N parameters
mark(transition: ...)      // how this thing enters
slide(a, b, c)             // frames, written out
build(a, b, c)             // frames that accumulate
reveal(n, (step, at) => ...) // frames that stay put
layers(key, a, b)          // an assembly that grows
mark(key, anim: ...)       // it moves on its own
deck(transition:, duration:, ...) // how pages turn
```

Something is in two places?

mark, one key

A page grows a line at a time?

build: the later parts push the layout

Parts arrive but nothing may shift?

reveal: what is to come holds its space

A drawing gains something outside itself?

layers: what was there glides as one picture

A curve must bend, a pose must change?

tween: a transition only cross-fades

It must move with nobody pressing?

tween(play:), waapi.animate

Out of reach: z-order, silently clipped overflow, a bitmap halfway through a big size change.